


# Fox Transfer Closure System

## Process Description

Fox Refueling Transfer Closure System is a dual double acting valve system designed to protect the Stormwater course during fuel transfer operations and the the holding tank from unwanted inflows of clean water during rain events.

System will activate closing the Stormwater(SW) Valve and opening the Holding tank(HT) Valve when either lid 1 or 2 of the fill points is lifted. This ensures that any unforeseen spills cannot enter the stormwater network during a fuel transfer operation. Once both lids are closed the system will revert back to stormwater mode opening the SW Valve and Closing the HT Valve

The system control panel has valve status indicator lights and a safe to commence operations Strobe which will only flash once both valves are in the correct position.



	This Drawing and design is the Property of Fox Environmental Systems Pty Ltd. It must not be used for any other purpose than that for which it was issued.	Project <b>System Specifications</b>	Drawing Title <b>Fox Transfer Closure System</b>	Drawn by: JFS	Scale: 1:20
				Date: 16/07/14	Drawing No: JN-